

कार्यालय-डा0 भीमराव अम्बेडकर सामाजिक परिवर्तन स्थल (आन्तरिक),

प्रशासनिक भवन (आन्तरिक), गोमती नगर, लखनऊ।

(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन सुरक्षा एवं अनुरक्षण समिति लखनऊ।)

पत्रांक :- 1383/प्र0/सा0परि0स्थ0-01/2023

दिनांक : 7/10/2023

कोटेशन आमन्त्रण सूचना

डा0 भीमराव अम्बेडकर सामाजिक परिवर्तन स्थल (आन्तरिक क्षेत्र) गोमती नगर, लखनऊ के 33/11 के0वी0 सब-स्टेशन नं0-3 निकट भागदारी भवन में 2000 के0वी0ए0 के ट्रांसफार्मर व पैनल आदि उपकरणों में नयी पाइप अर्थिंग सम्बन्धित कार्य कराये जाने हेतु सक्षम स्तर से प्राप्त अनुमति दिनांक 04.10.2023 के अनुपालन में निम्न विवरण के अनुसार कार्य किये जाने हेतु लखनऊ विकास प्राधिकरण में पंजिकृत टेकेदार / फर्मों से कोटेशन आमंत्रित किये जाते हैं। कार्य सम्बन्धित विवरण निम्नवत है:-

S.No	Description of work	Qty.	Unit
01	Dismantling reinforced cement concrete or reinforced brick work including stacking of dismantled materials as directed by the Engineer-in-Charge within a distance of 60 metres (200 ft.) (PWD, 694)	0.900	Cum
02	Boring /Drilling bore well of required dia for casing/strainer pipe by suitable method prescribed in IS 2800 (Part I) including collecting samples from different strata, preparing and submitting strata chart/bore log, including ghira & running charges of all equipments, tools, plants & machineries required for the job all complete as per director of Engineer in charge, up to 90 tr. depth below groundlevel.		
	0.00-15.00 M BGL	90	RM
	15.00 - 18.00 M BGL	18	RM
03	Lowering column pipe 50 mm dia in bore well with clamp and end cap.	06	Job
04	Providing and fixing of ball plug/bottom plug of required dia to the bottom of pipe assembly of tube well as per IS : 2800 (Part I) including necessary bolts and nuts of required size complete. 50 mm dia	12	Nos.
05	Providing and fixing of M.S.Clamp of required dia to the top of casing/ housing pipe of tube well as per IS : 2800 (Part I) including necessary bolts and nuts of required size complete. 50 mm dia	12	Nos.
06	Providing and laying in position cement concrete of specified grade excluding the centering and shuttling . All work up to plinth level. 1::6 (1 cement :3 course sand (zone III) : 6 graded stone aggregate 20mm. (Nominal size)	0.900	Cum.
07	Supply and laying of 50mm x 6mm G.I. strip from earth pipe directly in the ground as required complete in all respect. (PWD SOR 717, 2018)	132	RM
08	Supply and fixing 30 cm square C.I. frame with hinged cover & masonry housing and making chamber with Brick, cement, Coarse Sand .	06	Nos.

इच्छुक फर्म दिनांक 09.10.2023 सायं 05.00 बजे तक अपनी कोटेशन प्रबन्धक, डा0 भीमराव अम्बेडकर सामाजिक परिवर्तन स्थल (आन्तरिक) गोमती नगर, लखनऊ को प्रेषित करें, निर्धारित समय उपरान्त कोटेशन/प्रस्ताव स्वीकार नहीं होंगे। प्राप्त कोटेशन में से न्यूनतम दर वाली फर्म को कार्य करने हेतु कार्यदेश जारी किया जायेगा।

(यमन हफीज)
प्रबन्धक

प्रतिलिपि :

1. मुख्य प्रबन्धक महोदय को सादर अवलोकनार्थ।

2. प्रबन्धक (वित्त)/प्रबन्धक (अनुरक्षण) को सूचनार्थ।

3. सर्वर एवं नेटवर्क इंजीनियर को इस आशय से प्रेषित कि उक्त कोटेशन आमन्त्रण सूचना को स्मारक समिति की वेबसाइट पर अपलोड सम्बन्धित कार्यवाही हेतु।

4. नोटिस बोर्ड।

(यमन हफीज)
प्रबन्धक