

मुख्यालय (वित्त / लेखानुभाग)

स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन, सुरक्षा एवं अनुरक्षण समिति, लखनऊ।
मुख्य प्रशासनिक भवन, कक्ष संख्या-15, रमाबाई अम्बेडकर मैदान एवं अन्य विभिन्न सम्बद्ध क्षेत्र, शारदा नगर, लखनऊ-226002

Email ID: ho.ssps@yahoo.in

पत्रांक-346 / प्र0(वि0) / गैर वेतन-185 / स्मा0समिति / 2023-24

दिनांक: 11/01/2024

कोटेशन आमंत्रण सूचना

स्मारक समिति के मुख्य प्रशासनिक भवन के कक्ष संख्या-15 व 16 (वित्त/लेखानुभाग) में फाल सिलिंग एवं पर्दे लगाये जाने का कार्य कराया जाना है जिसका विवरण निम्नवत् है:-

S. No	Item	Qty.	Unit
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections. Power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS: 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm at 1200 mm centre ot centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50 long with 6 mm dia bolts other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts kof required size and other end of angle hanger fixed with intermediate G.I.channels 45*15*0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each aving lips of 10.5 mm, at 450 mm centre ot centre shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction including fixing perimeter channels 0.5 mm thich 27 mm high having flanges of 20 mm and 30 mm long the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25 mm long dry wall screws @ 230 mm interval including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5x25 mm at 230 mm c/c including joining and finishing to a flush finish of lapered and squaer edges of the board with recommended joining compppoud, jointing lates, finishing with jointing compound in 3 layers convering upto 150 mm on both sides of joint and two coats of prime suitable for board, all as per manufacture's specification and also including the cost of making opening for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawing specification and direction of the Engineer in charge but excluding the cost of painting with:12.45.3- 12.5 mm thick tapered edge gypsum moisture resistant board (DAR- No. 12.45)	30.00	sqm
2	S/F of Vertical blind etc. all complete work PSR	20.00	sqm

अतः लखनऊ विकास प्राधिकरण में पंजीकृत फर्मों से कोटेशन आमंत्रित किये जाते हैं। इच्छुक फर्म दिनांक-15.01.2024 की सांय तक अपना-अपना कोटेशन अधोहस्ताक्षरी कार्यालय में जमा कर सकते हैं। अवधि समाप्त होने के पश्चात कोटेशन स्वीकार नहीं किये जायेगे। कोटेशन स्वीकृत/निरस्त करने का अधिकार सक्षम अधिकारी को होगा।

नियम व शर्तें:-

- आपूर्ति किये गये कार्य की वारण्टी/गारण्टी 06 माह अथवा उत्पादन कम्पनी द्वारा दी गयी वारण्टी में जो भी अधिक हो लागू होगी।
- किसी भी प्रकार की टूट-फूट की जिम्मेदारी फर्म की होगी, जिसके सापेक्ष में किसी भी प्रकार का भुगतान नहीं किया जायेगा।
- किसी भी आकस्मिक स्थिति/समय कार्य पूर्ण न होने की दशा में समस्त जिम्मेदारी पूर्णतया फर्म की होगी।
- कार्यादेश जारी होने में अंकित अवधि में ही कार्य पूर्ण किया जाना होगा।

(देवेन्द्र मणि उपाध्याय)
प्रबन्धक (वित्त)

प्रतिलिपि:-

- सर्वर नेटवर्क इंजीनियर को इस आशय से प्रेषित कि उक्त कोटेशन आमंत्रण सूचना को स्मारक समिति की वेबसाइट पर अपलोडिंग संबंधी कार्यवाही हेतु।
- अन्य सम्बन्धित/गार्ड फाइल।

(देवेन्द्र मणि उपाध्याय)