पासी किला चौराहा, आशियाना, लखनऊ।

(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन, सुरक्षा एवं अनुरक्षण समिति, लखनऊ)

website:-www.smaraksamiti.org

e-mail id:-managersanskritik@gmail.com

ज्ञिङ 58। /मा०कां०सा०स्थ०/कोटेशन/2025,

दिनांक : 21 67-/2025

## कोटेशन आमंत्रण सूचना

मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल में स्थित ट्वॉयलेट की मरम्मत एवं वॉटर टैंक की सफाई आदि के कार्य हेतु लखनऊ विकास प्राधिकरण में पंजीकृत ठेकेदारों/फर्मों से कोटेशन आमंत्रित किया जाता है।

S.No.	Particulars of Item	Qty	Un
	Providing and first DMS	3	4
1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 40 mm dia. DSR 2023/17.28.2.2		No
2	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required: Size 600x450x200 mm. DSR 2023/17.11.2		No
3	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to Eureopean type W.C. of quality and make as approved by Engineer - in - charge. DSR 2023/17.16A	1.00	No
4	Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40 mm flush bend, 20 mm over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: White vitreous china dual purpose WC pan with white solid plastic seat and lid with white vitreous china flushing cistern and C.P. flush bend. DSR 2023/17.68.1	1.00	Nos
5	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete. 25 mm nominal bore. DSR 2023/18.18.3	2.00	Nos
6	Providing and fixing brass ferrule with C.I. mouth cover including boring and tapping the main : 25 mm nominal bore. DSR 2023/18.20.3	2.00	Nos
7	Providing and fixing uplasticised PVC connection pipe with brass unions: 45 cm length 15 mm nominal bore. DSR 2023/18.21.2.1	8.00	Nos
8	Door closer Godrej or equivalent etc. all complete work. Including supply of T&P all complete work. Chapter-1/20(a) Sanction Rate	10.00	Nos
9	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete . DSR 2023/14.34	6.00	Nos
10	Cleaning of terrace/loft water storage tank (inside surface area) upto 2000 litre capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank, including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba, all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre if during cleaning any Gl fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account). DSR 2023/14 754	4000.00	ltr
11	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931. 15 mm nominal bore. DSR 2023/18.53.1	14.00	Nos
12	Supply, Installation, laying & commissioning of HDPE Flange with tail piece, packing & nut bolt complete in all respect. Sanctioned rate Attached.	4.00	Nos
13	Supply, Installation, laying & commissioning of Elbow 90 mm. Sanctioned rate Attached	1.00	Nos
14	Arrangement of plumber. Sanctioned rate Attached.	2.00	Nos
15	Arrangement of Labour. Sanctioned rate Attached.	2.00	Nos
15	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50m outside the periphery of the area cleared. DSR 2023/2.31	40.00	Sqm

डच्छुक ठेकेदार/फर्म **दिनांक 31.07.2025 को अपराह्न 3:00 बजे तक** अपना कोटेशन, *पंजीकरण प्रमाणपत्र* संलग्न करते हुए सीलबन्द लिफाफे में प्रबन्धक कार्यालय, मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल,

पासी किला चौराहा, आशियाना, लखनऊ।

(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन, सुरक्षा एवं अनुरक्षण समिति, लखनऊ)

website:-www.smaraksamiti.org

e-mail id:-managersanskritik@gmail.com

GSTIN: 09AAFAS4562DIZG

निकटः पासी किला चौराहा, शारदा नगर, लखनऊ को उपलब्ध कराना अनिवार्य होगा। समय उपरान्त कोटेशन प्राप्त होने की स्थिति में कोटेशन पर विचार नहीं किया जायेगा। कोटेशन स्वीकृत/निरस्त करने का अधिकार सक्षम अधिकारी के अधीन होगा।

#### नियम व शर्ते

 कार्य के दौरान किसी भी प्रकार की टूट-फूट की सम्पूर्ण जिम्मेदारी फर्म की होगी।
कार्य के दौरान किसी भी प्रकार की जनहानि की जिम्मेदारी फर्म को वहन करना होगा। स्मारक सिमिति से कोई लेना-देना नहीं होगा।

3. कार्य मानक व गुणवत्ता के अनुरूप किया जाना होगां।

(अभिनव सिंह) प्रबन्धक

प्रतिलिपि:- निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

- 1. मुख्य प्रबन्धक महोदयं को सादर अवलोकनार्थ।
- 2. सर्वर एवं नेटवर्क इंजीनियर, स्मारक समिति।
  - 3. नोटिस बोर्ड पर चस्पा हेतु।
  - 4. अन्य सम्बन्धित।

पासी किला चौराहा, आशियाना, लखनऊ।

(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन, सुरक्षा एवं अनुरक्षण समिति, लखनऊ) website:-www.smaraksamiti.org

e-mail id:-managersanskritik@gmail.com

GSTIN: 09AAFAS4562DIZG

पत्रांक 58२/मा0कां0सा0स्थ0/कोटेशन/2025,

दिनांक : 21 /0 7/2025

## कोटेशन आमंत्रण सूचना

मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल में स्थापित 20 मीटर के 01 अदद हाईमास्ट पोल एवं 10 मीटर के 15 अदद स्ट्रीट पोल उतारने एवं पुनः लगाने के कार्य हेतु लखनऊ विकास प्राधिकरण में पंजीकृत ठेकेदारों/फर्मों से कोटेशन आमंत्रित किया जाता है।

S.No.	Particulars of Item	Qty	Unit
1	2	3	4
1	Dismantling and fixing for Labour of 20 mtr High mast shaft of approved make with rising system hot dip galvanized inside & outside dip, heaving pole sheet thickness 4 mm. Top dia minimum 150 mm, Bottom dia 410 mm base plate 32 mm thick suitable for wind velocity as per IS 875 part 3 & ha ving no circumferential weld, with accessories for high mast such as head frame suitable for 6 to 12 luminaries & its control gear boxes 1.5 HP power tool moter, 3 point suspension system with steel wire rope 8 mm dia, double drum winch, including making suitable foundation as per manufacture drawing/ sire regiment along with foundation bolts nuts, washers, anchor plates etc complete in all respect.	01	Nos.
2	Dismantling and fixing for Labour of 10 mtr GI Octagonal Pole of approved make (top dia 100 mm, Bottom dia 200 mm and base plate 16 mm thick) having 3 mm thickness with Single arm bracket 1 Mtr. length in 1:2:4 RCC foundation bolt including the cost of foundation, excavation & back filling and Required T&P complete in all respect.	15	Nos.
3	Dismantling and fixing of 32 mm x 6 mm G.I. strip from earth electrode directly in the ground as required complete in all respect.	15	Mtr.
4	Supply and Fixing of Same as in item 291 but with 3 nos. 4 sq mm and 2 nos. 2.5 sq mm FRLSH PVC insulated copper conductor cable.	50	Mtr.

इच्छुक ठेकेदार /फर्म दिनांक 31.07.2025 को अपराह्न 3:00 बजे तक अपना कोटेशन, पंजीकरण प्रमाणपत्र की छायाप्रति संलग्न करते हुए सीलबन्द लिफाफे में प्रबन्धक कार्यालय, मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल, निंकटः पासी किला चौराहा, शारदा नगर, लखनऊ को उपलब्ध कराना अनिवार्य होगा। समय उपरान्त कोटेशन प्राप्त होने की स्थिति में कोटेशन पर विचार नहीं किया जायेगा। कोटेशन स्वीकृत/निरस्त करने का अधिकार सक्षम अधिकारी के अधीन होगा।

#### नियम व शर्ते

- 1. कार्य के दौरान किसी भी प्रकार की टूट-फूट की सम्पूर्ण जिम्मेदारी फर्म की होगी।
- 2. कार्य के दौरान किसी भी प्रकार की जनहानि की जिम्मेदारी फर्म को वहन करना होगा। स्मारक समिति से कोई लेना-देना नहीं होगा।
- 3. कार्य मानक व गुणवत्ता के अनुरूप किया जाना होगा।

प्रतिलिपि:- निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

- 1. मुख्य प्रबन्धक महोदय को सादर अवलोकनार्थ।
- 2. सर्वर एवं नेटवर्क इंजीनियर, स्मारक समिति।
  - 3. नोटिस बोर्ड पर चस्पा हेतु।
  - 4. अन्य सम्बन्धित।

(अभिनव सिंह) प्रबन्धक

पासी किला चौराहा, आशियाना, लखनऊ।

(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन, सुरक्षा एवं अनुरक्षण समिति, लखनऊ)

website:-www.smaraksamiti.org

e-mail id:-managersanskritik@gmail.com

GSTIN: 09AAFAS4562DIZG

पत्रांक 583/मा0कां0सा0स्थ0/कोटेशन/2025,

दिनांक : 21 /07-/2025

## कोटेशन आमंत्रण सूचना

मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल में स्थापित प्याऊ की मरम्मत एवं पेंटिंग के कार्य हेतु लखनऊ विकास प्राधिकरण में पंजीकृत ठेकेदारों/फर्मों से कोटेशन आमंत्रित किया जाता है।

S.No.	Particulars of Item	Qty	Unit
1	2	3	4
1	Removing Dry or Oil Bound Distemper, water proofing cement paint and the like by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. Complete. (DSR 2023/13.91)	99.80	Sqm
2	Providing and applying white cement based putty of average thickness 1 mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. DSR 2023/13.80	99.80	Sqm
3	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour: New work (two or more coats) over and including Water thinnable priming coat with cement primer having VOC content less than 50 gram/litre. DSR 2023/13.41.1	99.80	Sqm

इच्छुक ठेकेदार/फर्म **दिनांक 26.07.2025 को अपराह्न 3:00 बजे तक** अपना कोटेशन, पंजीकरण प्रमाणपत्र की छायाप्रति संलग्न करते हुए सीलबन्द लिफाफे में प्रबन्धक कार्यालय, मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल, निकटः पासी किला चौराहा, शारदा नगर, लखनऊ को उपलब्ध कराना अनिवार्य होगा। समय उपरान्त कोटेशन प्राप्त होने की स्थिति में कोटेशन पर विचार नहीं किया जायेगा। कोटेशन स्वीकृत/निरस्त करने का अधिकार सक्षम अधिकारी के अधीन होगा।

#### नियम व शर्ते

1. कार्य के दौरान किसी भी प्रकार की टूट-फूट की सम्पूर्ण जिम्मेदारी फर्म की होगी।

2. कार्य के दौरान किसी भी प्रकार की जनहानि की जिम्मेदारी फर्म को वहन करना होगा। स्मारक समिति से कोई लेना-देना नहीं होगा।

3. कार्य मानक व गुणवत्ता के अनुरूप किया जाना होगा।

(अभिनव सिंह)

प्रतिलिपि:- निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

1. मुख्य प्रबन्धक महोदयं को सादर अवलोकनार्थ।

सर्वर एवं नेटवर्क इंजीनियर, स्मारक समिति।

3. नोटिस बोर्ड पर चस्पा हेतु।

4. अन्य सम्बन्धित।

(अधिनव-सिंह) प्रकृधका २-2S