

कार्यालय : प्रबन्धक
बौद्ध विहार शान्ति उपवन, लखनऊ
(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों आदि की प्रबन्धन सुरक्षा एवं अनुरक्षण समिति, लखनऊ)

पत्रांक- **114** / बौ0वि0शा0उप0 / 2026-27

दिनांक : **25.07.2026**

कोटेशन आमन्त्रण सूचना

स्मारक समिति के प्रबन्धाधीन बौद्ध बौद्ध विहार शान्ति उपवन, लखनऊ के अन्तर्गत मुख्य स्टोर में एल्यूमीनियम पार्टीशन कराये जाने से सम्बन्धित कार्य कराये जाने हेतु लखनऊ विकास प्राधिकरण, लखनऊ में पंजीकृत ठेकेदारों/फर्मों से कोटेशन आमंत्रित किया जाता है।

S.N.	Description of work	Qty	Unit	Rate/ item
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Zsections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) DSR 2023 Item No. 21.1.2.2	83.57	kg	41,883.61
2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Gradel Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides DSR 2023 Item No.21.2.2	22.52	sqm	19,842.60
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm) DSR 2023 Item No.21.3.2	6.84	sqm	8133.24
4	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete: 250x16mm(DSR 2023 Item No. 9.62.2)	2	Each	306.02
5	Providing and fixing ISI marked oxidized M.S. tower bolt black finish (Barrel type) with necessary screws etc. complete. 150x10mm (DSR 2023 Item No. 9.63.3)	2	Each	93.92

इच्छुक ठेकेदार/फर्म दिनांक 30.07.2026 को अपराह्न 04:00 बजे तक अपना कोटेशन, पंजीकरण प्रमाण-पत्र की छायाप्रति संलग्न करते हुए सीलबन्ध लिफाफे में प्रबन्धक, बौद्ध विहार शान्ति उपवन, पकरी का पुल, आलमबाग, लखनऊ को उपलब्ध कराना अनिवार्य होगा। निर्धारित समय उपरान्त कोटेशन प्राप्त होने की स्थिति में कोटेशन पर विचार नहीं किया जायेगा। कोटेशन स्वीकृत/निरस्त करने का अधिकार सक्षम अधिकारी के अधीन होगा।

नियम व शर्तें:

- 01- कार्य के दौरान किसी भी प्रकार की टूट-फूट की सम्पूर्ण जिम्मेदारी फर्म की होगी
- 02- कार्य के दौरान किसी भी प्रकार की जनहानि की जिम्मेदारी फर्म को वहन करना होगा। स्मारक समिति से कोई लेना-देना नहीं होगा।
- 03- कार्य मानक व गुणवत्ता के अनुरूप किया जाना होगा।
- 04- कार्य पूर्ण होने के उपरान्त कार्य की वारण्टी 06 माह की होगी।

(मनीष कुमार मौर्य)
प्रबन्धक

प्रतिलिपि:

- 01- प्रबन्धक (अनुरक्षण/वित्त), स्मारक समिति।
- 02- प्रभारी, आई0टी0 सेल को इस आशय से प्रेषित कि उक्त कोटेशन आमन्त्रण सूचना को स्मारक समिति की वेब साइट www.smaraksamiti.org पर अपलोड करने का कष्ट करें।
- 03- सहायक प्रबन्धक/व्यवस्थापक को सूचनार्थ।
- 04- नोटिस बोर्ड पर चस्पा हेतु।

कार्यालय, एन.ए. प्रौद्योगिकी प्रकोष्ठ

पत्र/पत्रावली प्राप्ति संख्या... **1.24**

प्राप्ति दिनांक... **27/07/2026**

संलग्नक..... पत्रा: प्रशासनिक भवन, पकरी का पुल, आलमबाग, लखनऊ।

website - www.smaraksamiti.org

e-mail id - baudhviharmanager@gmail.com

(मनीष कुमार मौर्य)
प्रबन्धक