

कार्यालय
मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल, लखनऊ।
(स्मारकों, संग्रहालयों, संस्थाओं, पार्कों व उपवनों, आदि की प्रबन्धन, सुरक्षा एवं अनुरक्षण समिति, लखनऊ)

पत्रांक सं० 604/प्र०/मा०का०सा०स्थ०/2026

दिनांक : 30/09/26

कोटेशन आमन्त्रण सूचना

स्मारक समिति के प्रबन्धाधीन मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल, लखनऊ के परिक्षेत्र में नये विद्युत पैनल 200 एम्पियर की आपूर्ति एवं स्थापना सम्बन्धी कार्य कराये जाने हेतु आगणन की मुख्य अभियंता, ल०वि०प्रा० एवं वित्त नियंत्रक, ल०वि०प्रा० महोदय द्वारा प्रदत्त अनुमति दिनांक 25.09.2025 एवं 28.09.2026 के क्रम में निम्न विवरण के अनुसार कार्य हेतु ल०वि०प्रा० में पंजीकृत विभिन्न फर्मों से कोटेशन आमन्त्रित किये जाते हैं।

S.N.	Description	Qty.	Unit	Rate
01	Supply and erection of factory fabricated and wired metal clad dust and vermin proof floor mounting panel TPN switch board complete with the following HRC type heavy duty TPN fuse switches with fuses and instruments chamber etc. complete in all respect. The instrument chamber shall be separate and shall comprise of flush type ammeter, voltmeter, instrument fuses, current transformer etc. The board shall have suitable capacity electrolytic aluminium bus bars as per IS8623 insulate with heat shrink sleeving and mounted on non-hygroscopic supports such as CMC/DMC support with detachable side covers and shall be suitable for extension on the sides. The switches shall be complete with suitable cable end boxes, revers entry boxes in case of pedestal type, cable sockets, compression glands and indicating lamp on incoming etc. The job includes the grouting of the board as per direction of Engineer-in-charge. II and pedestal type for Cat B and C only. Incoming - TPN 200 Amp (MCCB) x 01 No., Outgoing - TPN 100 Amp (MCCB) x 02 Nos.	01	no.	76700.00
02	Supply and burring of safe earthing electrode T-19 (Hot Dip Galvanized), Length up to 2000mm, outer dia 50mm inner Dia 25mm, terminal Dia 12mm outer GI pipe 16 swg and inner GI pipe of 12 swg with Hot Dip Galvanization up to 100 micron filled with crystalline conductive mixture (CCM) having anti corrosive & conductive property with 50kg. activated soil (BFC) capable of reducing the soil resistivity with good mixture of retaining capacity and one earthing lead of 25mm x 3mm GI strip, up to switch board (from apron switch board, the coast of G.I. strip will be extra) along with 30 cm square C.I. frame with hinged cover & masonry housing.	01	No.	6450.00
03	Supply and laying of 25mm x 3mm G.I. strip from earth electrode directly in the ground as required complete in all respect.	05	Mtr.	90.00


उपरोक्त के क्रम में लखनऊ विकास प्राधिकरण में पंजीकृत इच्छुक फर्मों दिनांक 05.10.2026, सायं 04.00 बजे तक अपनी कोटेशन प्रबन्धक कार्यालय, मान्यवर श्री कांशीराम जी सांस्कृतिक स्थल, लखनऊ को प्रेषित कर सकते हैं। निर्धारित समय उपरान्त कोटेशन/प्रस्ताव स्वीकार्य नहीं होंगे। प्राप्त कोटेशन में से न्यूनतम दर वाली फर्म को कार्य करने हेतु कार्यदेश जारी किया जायेगा।

/

(अभिनव सिंह)
प्रबन्धक

प्रतिलिपि:- पत्रांक व दिनांक उक्तवत्।

1. मुख्य प्रबन्धक महोदय को सादर अवलोकनार्थ।
2. प्रबन्धक (वित्त/अनुरक्षण) को सूचनार्थ।
3. आई०टी० प्रभारी महोदय/सर्वर एवं नेटवर्क इंजीनियर को इस आशय से प्रेषित कि उक्त कोटेशन आमन्त्रण सूचना को स्मारक समिति की वेबसाइट पर अपलोड सम्बन्धित कार्यवाही कर सकें।
4. नोटिस बोर्ड।


प्रबन्धक